

# Fort River Elementary School

## Feasibility Study – Community Presentation

February 13<sup>th</sup>, 2019



**TSKP** ARCHITECTURE | PLANNING | INTERIORS  
STUDIO



# Fort River School | Community Involvement



## Presentation Goals:

1. Introduction to TSKP STUDIO
2. Update on Feasibility Study
3. Review the Options
4. Discuss Cost Factors
5. Request Feedback



## Design Quality | Simple... Child Friendly





## Design Quality | Age Appropriate Scale





## Design Quality | Natural Light... Welcoming





## Design Quality | Multi-functioning Space





## Design Quality | Beautiful and Durable






## Design Quality | Connections to the Outdoors





# Design Quality | Security + Safety





# Existing Conditions Investigations



# Existing Conditions | Summary

## 1. Deferred Capital Infrastructure Replacement Items

- ✓ Roof
- ✓ HVAC system
- ✓ Electrical system
- ✓ Window Replacement

## 2. Unsatisfied Educational Needs

- ✓ Open Classrooms
- ✓ Accessibility
- ✓ Lighting
- ✓ Communication Systems
- ✓ Technology Infrastructure
- ✓ Interior Environment


## 3. Security

- ✓ Access Control
- ✓ Passive Surveillance, Building Exterior hardening, Classroom Security





# Existing Conditions | Summary



Educational Facilities Laboratories c. 1958, - "Schools Without Walls"





Existing Conditions | Open Classrooms





## Existing Conditions | Daylighting





# Educational Space Needs



# Educational Space Needs | Right Size

	Fort River Study Range				MSBA guidelines
K-6 Enrollment	315 ← → 420				420
Pre-K Enrollment (FTE)	0	45	0	45	45
Total Enrollment	315	360	420	465	465
Total Building Gross Floor Area	70,000	77,000	78,000	84,000	72,742

## Compared to MSBA guidelines:

Amherst Classroom Guidelines		4,725
District SE (AIMS, Bldg. Blocks)		5,917
Pre-K Administration and Support		1,743
MSBA guideline (adjusted)		85,127



# Educational Space Needs | Fort River Rooms + Educational Program

Fort River School Building Project Educational Program	
2	
<b>Table of Contents</b>	
Amherst Public Schools District Mission.....	1
Guiding Principles.....	3
21 <sup>st</sup> Century Learning Goals.....	3
Grade & School Configuration Policies.....	4
Class Size Policies.....	5
School Scheduling Method.....	5
Teaching Methodology and Structure.....	10
Technology Infrastructure, Policies & Requirements ..	18
Teacher Planning and Room Assignment Policies.....	20
Special Education Programs.....	21
ELL Program.....	24
Transportation Policies.....	24
Lunch Programs .....	25
Functional Relationships & Key Adjacencies.....	25
Security & Visual Access Requirements.....	26
Acknowledgments.....	28

Page | 2

3/16/16  
Rev. 8/31/18

CORE ACADEMIC SPACES	
Pre-Kindergarten w/ toilet	3
Kindergarten w/ toilet	3
General Classrooms - Grade 1-6	18
Computer Lab / Maker Space	1
Break out Teaching Space (1 per grade 1-6)	6

SPECIAL EDUCATION	
Large group SE	1
Small group SE	2
Self-Contained SPED - toilet	3
AIMS Program	1
AIMS Program - Reflection Room	1
Building Blocks Program	2
Building Blocks Program - Reflection Room	2
ELL classrooms	2
Speech	2
Math	1
Assessment Room	1
Sensory	1
Office for ETL	1
Reflection Room	2
Reading	2
Occupational Therapy / Physical Therapy	1
Speech for PK	1
OT/PT for PK	1
Behavior Analyst for PK	1

ART & MUSIC	
Art Classroom - 25 seats	1
Art Workroom w/ Storage & kiln	1
Music Classroom / Large Group - 25-50 seats	1
Instrumental Music (6-8 students)	2

HEALTH & PHYSICAL EDUCATION	
Gymnasium	1
Gym Storeroom	1
Health Instructor's Office w/ Shower & Toilet	1

MEDIA CENTER	
Media Center / Reading Room	1

DINING & FOOD SERVICE	
Cafeteria / Dining	1
Stage	1
Chair / Table / Equipment Storage	1
Kitchen	1
Staff Lunch Room	1

MEDICAL	
Medical Suite Toilet	1
Nurses' Office / Waiting Room	1
Examination Room / Resting	2

ADMINISTRATION & GUIDANCE	
General Office / Waiting Room / Toilet	1
Teachers' Mail and Time Room	1
Duplicating Room	1
Records Room	1
Principal's Office w/ Conference Area	1
Principal's Secretary / Waiting	1
Assistant Principal's Office	1
Supervisory / Spare Office	1
Conference Room	1
Guidance Office	2
Guidance Office	1
Guidance Storeroom	1
Teachers' Work Room	2
Psychologist's Office	1
Parent Room	1
PK Coordinator w/Conf	1

CUSTODIAL & MAINTENANCE	
Custodian's Office	1
Custodian's Workshop	1
Custodian's Storage	1
Recycling Room / Trash	1
Receiving and General Supply	1
Storeroom	1
Network / Telecom Room	1



# **Sustainability and Net Zero**



# What makes it sustainable?

- Safe and Healthy
- Resource Efficient
- Flexible and Adaptable
- Durable and Maintainable






## Minimum Requirements for funding:

- 1) LEED v4 Certified, or NE-CHPS Verified
- 2) 10% better than energy code


2% additional reimbursement for projects that can exceed energy code by at least 20%



# Energy Codes and LEED Requirements







Source: Federal R&D Agenda for Zero-Net Energy high Performance Green Buildings, National Science and Technology Council, October 2008



# Design Options



# Design Options | Range of Options



NEW BUILDING

A



2 STORY ADDITION

B



1 STORY ADDITION

C



TWO SMALL  
ADDITIONS

D



SMALL ADDITION

E



BASE REPAIR

F



100%  
NEW

50%  
NEW

29%  
NEW

18%  
NEW

7%  
NEW

0%  
NEW

Simplest  
construction  
phasing


Complicated  
construction  
phasing



# Design Options | **Non-Negotiables**


Included in Options A – E:

- ✓ Natural Light in all Classrooms
- ✓ Good air quality / ventilation / circulation
- ✓ Good Acoustics (ANSI S12.60)
- ✓ Elimination of open classroom design
- ✓ Compliance with Town's Net Zero bylaw
- ✓ Sustainable design
- ✓ Flexibility in case of increased enrollment in the future
- ✓ Adequate space for program needs
- ✓ Cost and Environmental analysis that includes construction, demolition, swing space, operations
- ✓ Accessible
- ✓ Building and Energy code compliance






100% NEW



AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION A




DRAFT




AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION A





1 FIRST FLOOR PLAN  
1" = 30'-0"

AMHERST, FORT RIVER SCHOOL  
OPTION A, A.I



AMHERST, FORT RIVER SCHOOL  
OPTION A, A.I




50% NEW



AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION B




DRAFT



AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION B



09/25/18



AMHERST, FORT RIVER SCHOOL NEW, RENO, DEMO, OPTION B<sup>31</sup>



# TSKP STUDIO

10/22/18

## ROOM TYPE KEY

- ADMINISTRATION
- ART & MUSIC
- CORE ACADEMIC SPACES
- CUSTODIAL & MAINTENANCE
- DINING & FOOD SERVICE
- HEALTH & PHYSICAL EDUCATION
- MEDIA CENTER
- MEDICAL
- NON-PROGRAMMED SPACES
- OTHER
- SPECIAL EDUCATION
- STORAGE
- TOILET ROOMS

LEVEL 2: 18,400 SF  
LEVEL 1: 69,000 SF  
TOTAL: 87,400 SF

ACCESS TO  
PK PLAY

PK ENTRY

MAIN ENTRY

ACCESS TO  
FIELDS, PLAY

1 FIRST FLOOR PLAN  
1" = 30'-0"

AMHERST, FORT RIVER SCHOOL

OPTION B, B.1





1 SECOND FLOOR PLAN  
1" = 30'-0"

AMHERST, FORT RIVER SCHOOL

OPTION B, B.I.




29% NEW



AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION C




DRAFT



AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION C





AMHERST, FORT RIVER SCHOOL

NEW, RENO, DEMO, OPTION C



# TSKP STUDIO

10/22/18



AMHERST, FORT RIVER SCHOOL

OPTION C, C.I.




18% NEW



AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION D



DRAFT




AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION D



# TSKP STUDIO

09/25/18



AMHERST, FORT RIVER SCHOOL

NEW, RENO, DEMO, OPTION D



## 10/22/18



OPTION D, D.I 41



7% NEW



AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION E




DRAFT



AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION E



10/22/18



AMHERST, FORT RIVER SCHOOL      NEW, RENO, DEMO, OPTION E<sup>44</sup>



# TSKP STUDIO

10/22/18

## ROOM TYPE KEY


- ADMINISTRATION
- ART & MUSIC
- CORE ACADEMIC SPACES
- CUSTODIAL & MAINTENANCE
- DINING & FOOD SERVICE
- HEALTH & PHYSICAL EDUCATION
- MEDIA CENTER
- MEDICAL
- OTHER
- SPECIAL EDUCATION
- STORAGE
- TOILET ROOMS

TOTAL GSF: 81,300 SF

PK ENTRY

OPTION E.I. ELIMINATE 5,800 SF (NEW CONST. AREA)

1 FIRST FLOOR PLAN  
1" = 30'-0"



AMHERST, FORT RIVER SCHOOL

OPTION E, E.I





0% NEW

- Abatement
- Roof replaced
- Windows replaced
- Reconfigure restrooms, doors, walls, etc to be ADA accessible
- Replace mechanical systems. Keep existing boilers.
- Replace electrical, interior lighting, fire alarm.
- New Sprinkler System
- Ceilings and Floor finishes replaced.
- Re-paving existing asphalt areas and resetting granite curbing
- Replacing playground equipment and surfacing

## AMHERST FORT RIVER SCHOOL AERIAL VIEW OPTION F



# **Discuss Cost Factors**



Design Options | Cost Factor: Construction Phasing and Duration

DRAFT



NEW BUILDING  
85,000 SF

A



2 STORY ADDITION  
87,400 SF

B



1 STORY ADDITION  
79,768 SF

C



TWO ADDITIONS  
86,000 SF

D



SMALL ADDITION  
81,300 SF

E



BASE REPAIR  
78,000 SF

F





## Fort River School | Cost Factor : Path to Net Zero

### New Construction:

#### Targeting EUI 50

- Full Kitchen.
- Summer Programs – full building year round use.
- Double glazed windows with Low-E coating.
- R25 Walls.
- R30 Roof.
- VAV with energy recovery.
- LED lighting.

#### Targeting EUI 30

- Full Kitchen
- Summer Program for part of the building only.
- Relaxed interior temperatures:
  - Summer 77 to 78 degrees with lower humidity
  - Winter – 68 degrees.
- Triple Glazing
- R35 Walls
- R60 Roof
- R15 under slab
- Geothermal with Chilled Beam (or Geothermal with VRF)
  - Operational considerations for more complicated systems
- Radiant flooring on the ground floor

### Renovation:

#### Targeting EUI 50

- Full Kitchen.
- Summer Programs – full building year round use.
- New roof insulation R30
- New windows, double glazed with low E coating
- Use existing boilers (or go all electric with small geothermal heat pump?)
- VAV with energy recovery
- LED lighting.



#### Targeting EUI 30

- Full Kitchen
- Summer Program for part of the building only.
- Relaxed interior temperatures:
  - Summer 77 to 78 degrees with lower humidity;
  - Winter – 68 degrees.
- Roof Insulation R60
- Wall Insulation R35
- New Windows, triple glazing
- Geothermal with Chilled Beam (or Geothermal with VRF)
- Roof-top heat pumps (with electric backup)
- Geothermal with chilled beam (or Geothermal with VRF)
  - Operational considerations for more complicated systems



# Fort River School| Cost Factor: Path to Net Zero

DRAFT



Source: Federal R&D Agenda for Zero-Net Energy high Performance Green Buildings, National Science and Technology Council, October 2008

**If we target an Energy Use Intensity of 50 ...**  
the area of PV that is required is *ALL* of the pink shown in the site plan.

PV panel cost :	\$442,000 (project)*
Net Zero Premium:	\$442,000 (project)

**If we target an Energy Use Intensity of 30 ...**  
the area of PV that is required is reduced as noted in the site plan. *However, there is a cost increase building envelope and systems.*

PV panel cost :	\$265,000 (project)*
Increase for HVAC Option #4:	\$2,380,000 (project)
Increase for Envelope:	\$2,530,000 (project)
Net Zero Premium:	\$5,175,000 (project)

\* PV panels could be procured via a Power Purchase Agreement eliminating their cost to the project.

AMHERST, FORT RIVER SCHOOL SITE PLAN OPTION A



Fort River School| **Cost Factor : Mechanical System**

System Description	Plant	Initial Cost	Operational Cost	Maintenance	Equipment Filters in Zone
Option #1 – Air Cooled VRF	Air-Cooled (Electric)	2	5	2	Yes
Option #2 – Water Cooled VRF	Geothermal	5	3	4	Yes
Option #3 – Water Cooled VRF	Cooling Tower & Boiler	3	4	6	Yes
Option #4 – Water Cooled GSHP & Chilled Beams	Geothermal	6	1	3	No
Option #5 - Water Cooled HP & Chilled Beams	Cooling Tower & Boiler	4	2	5	No
Option #6 – VAV, DX RTU's	Air-Cooled (Electric)	1+	6	1	No

1 = Lowest

6 = Highest




Fort River School| Cost Factor: Procurement Method

DRAFT


<div><div><div>A.M. Fogarty</div><div>&amp; Assoc., Inc.</div></div><div><div>175 Derby St., Suite 5, Hingham, MA 02043</div><div>TEL: (781) 749-7272 • FAX: (781) 740-2652</div><div>ptm@amfogarty.com</div></div><div>"Construction Cost Consultants"</div></div>		
<div>Fort River Elementary School</div> <div>Amherst, MA</div> <div>November 30, 2018</div>		
GRAND SUMMARY		
DESIGN OPTIONS:	CHPT 149 A CM @ Risk	CHPT 149 DESIGN/BID
OPTION A TOTAL	\$46,951,674	\$42,256,507
OPTION A1 TOTAL	\$44,187,731	\$39,768,958
OPTION A2 TOTAL	\$43,792,882	\$39,413,594
OPTION A3 TOTAL	\$41,028,938	\$36,926,045
OPTION B TOTAL	\$43,194,409	\$38,874,968
OPTION B1 TOTAL	\$41,574,364	\$37,416,928
OPTION B2 TOTAL	\$40,920,662	\$36,828,595
OPTION B3 TOTAL	\$39,300,616	\$35,370,555
OPTION C TOTAL	\$39,282,624	\$35,354,362
OPTION C1 TOTAL	\$37,662,579	\$33,896,321
OPTION C2 TOTAL	\$37,008,877	\$33,307,989
OPTION C3 TOTAL	\$35,388,832	\$31,849,948
OPTION D TOTAL	\$41,068,734	\$36,961,861
OPTION D1 TOTAL	\$38,279,933	\$34,451,939
OPTION D2 TOTAL	\$39,121,376	\$35,209,238
OPTION D3 TOTAL	\$36,332,575	\$32,699,317
OPTION E TOTAL	\$39,484,534	\$35,536,080
OPTION E1 TOTAL	\$36,815,252	\$33,133,727
OPTION E2 TOTAL	\$37,641,518	\$33,877,367
OPTION E3 TOTAL	\$36,815,252	\$33,133,727
OPTION F TOTAL	\$22,545,379	\$20,290,841
<div>Prepared by: A. M. Fogarty &amp; Associates, Inc.</div> <div>FORT RIVER ELEM SCHOOL 12-1811/30/20183:30 PM</div>		
Page 1		




Construction  
Cost Only  
in \$Mill



A



B




C



D



E




F


DRAFT


	NEW				2 STORY ADDITION				SINGLE STORY ADDITION				MULTIPLE SMALL ADDITIONS				SMALL ADDITION				CODE REPAIR	
	A	A.1	A.2	A.3	B	B.1	B.2	B.3	C	C.1	C.2	C.3	D	D.1	D.2	D.3	E	E.1	E.2	E.3	F	
ENROLLMENT	465	420	360	315	465	420	360	315	465	420	360	315	465	420	360	315	465	420	360	315	315	
% NEW	100	100	100	100	50	53	55	59	29	31	32	35	18	12	18	12	7	0	8	0	0	
PRE-K INCLUDED?	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	N	
CONSTR. COST (HVAC SYS #1)	50.9	48.1	47.7	44.9	44.5	42.8	42.1	40.5	39.3	37.6	37	35.3	40.4	37.5	38.4	35.6	38.2	35.1	36.3	35.1	22.9	
CONSTR. COST (HVAC SYS #2)	52.5	49.5	49.1	46.2	46.1	44.4	43.6	41.9	40.8	39	38.3	36.6	42	39	39.9	36.9	39.7	36.5	37.7	36.5	24.4	
CONSTR. COST (HVAC SYS #3)	50.9	48.1	47.7	44.9	44.5	42.8	42.1	40.5	39.3	37.6	37	35.3	40.4	37.5	38.4	35.6	38.2	35.1	36.3	35.1	22.9	
CONSTR. COST (HVAC SYS #4)	52.8	49.9	49.5	46.5	46.5	44.7	44	42.2	41.1	39.3	38.6	36.8	42.4	39.4	40.2	37.2	40.1	36.8	38	36.8	24.7	
CONSTR. COST (HVAC SYS #5)	51.5	48.7	48.3	45.4	45.1	43.4	42.8	41.1	39.9	38.2	37.5	35.8	41	38.2	39	36.1	38.8	35.7	36.9	35.7	23.5	
CONSTR. COST (HVAC SYS #6)	50.5	47.7	47.3	44.5	44	42.4	41.8	40.1	38.9	37.3	36.6	35	39.9	37.2	38	35.2	37.8	34.7	36	34.7	22.5	





Total Project Cost in \$Mill  
\*Includes 0.5% for Art


  
**A**

  
**B**

  
**C**

  
**D**

  
**E**

  
**F**

	NEW				2 STORY ADDITION				SINGLE STORY ADDITION				MULTIPLE SMALL ADDITIONS				SMALL ADDITION				CODE REPAIR	
	A	A.1	A.2	A.3	B	B.1	B.2	B.3	C	C.1	C.2	C.3	D	D.1	D.2	D.3	E	E.1	E.2	E.3	F	
ENROLLMENT	465	420	360	315	465	420	360	315	465	420	360	315	465	420	360	315	465	420	360	315	315	
% NEW	100	100	100	100	50	53	55	59	29	31	32	35	18	12	18	12	7	0	8	0	0	
PRE-K INCLUDED?	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	Y	N	N	
PROJECT COST (HVAC SYS #1)	63.8	60.3	59.8	56.3	55.8	53.7	52.9	50.8	49.3	47.2	46.4	44.3	50.7	47.1	48.2	44.6	47.9	44	45.6	44	28.8	
PROJECT COST (HVAC SYS #2)	65.9	62.2	61.7	58	57.9	55.7	54.8	52.6	51.2	49	48.1	45.9	52.7	49	50	46.3	49.9	45.8	47.4	45.8	30.6	
PROJECT COST (HVAC SYS #3)	63.8	60.3	59.8	56.3	55.8	53.7	52.9	50.8	49.3	47.2	46.4	44.3	50.7	47.1	48.2	44.6	47.9	44	45.6	44	28.8	
PROJECT COST (HVAC SYS #4)	66.3	62.6	62.1	58.4	58.3	56.1	55.2	53	51.6	49.4	48.5	46.2	53.2	49.4	50.5	46.7	50.3	46.2	47.8	46.2	31	
PROJECT COST (HVAC SYS #5)	64.7	61.1	60.6	57	56.6	54.5	53.7	51.1	50.1	47.9	47.1	45	51.5	47.9	48.9	45.3	48.7	44.8	46.3	44.8	29.5	
PROJECT COST (HVAC SYS #6)	63.3	59.9	59.4	55.9	55.3	53.2	52.4	50.4	48.8	46.8	45.9	43.9	50.1	46.6	47.7	44.2	47.4	43.6	45.1	43.6	28.3	



Fort River School| Cost Benchmarks

DRAFT

DESCRIPTION	FORT RIVER	COST/SF	WILDWOOD	COST/SF	MAPLE	COST/SF
	ELEM. SCHOOL		ELEM. SCHOOL		ELEM. SCHOOL	
	11/30/18		7/26/16		7/3/18	
	85,000 GSF		122,272 GSF		177,370 GSF	
BUILDING COST	\$25,069,620	\$294.94	\$33,633,405	\$275.07	\$57,818,971	\$325.98
SITEWORK	\$5,640,994	\$66.36	\$5,385,927	\$44.05	\$8,527,301	\$48.08
HAZARDOUS WASTE REMOVAL ALLOWANCE	\$860,000	\$10.12	\$800,000	\$6.54	\$2,000,000	\$11.28
BUILDING DEMOLITION	\$585,000	\$6.88	\$492,000	\$4.02	\$919,128	\$5.18
PV PANELS	\$3,396,000	\$39.95	NIC		NIC	
TOTAL DIRECT COST	35,551,614	\$418.25	40,311,332	\$329.69	69,265,400	\$390.51
DESIGN CONTINGENCY	\$4,266,194	\$50.19	\$4,031,133	\$32.97	\$6,926,540	\$39.05
CM CONTINGENCY	\$1,194,534	\$14.05	\$898,136	\$7.35		
ESCALATION ( fall 2017 )	\$3,185,425	\$37.48	\$1,571,739	\$12.85	\$3,047,678	\$17.18
PRE CON	N/A		N/A			
GENERAL CONDITIONS	\$4,278,454	\$50.33	\$4,543,187	\$37.16	\$4,723,774	\$26.63
GENERAL REQUIREMENTS	\$1,424,933	\$16.76	\$1,396,150	\$11.42	\$1,494,776	\$8.43
INSURANCE	INC		INC		\$1,153,685	\$6.50
FEE	\$1,247,529	\$14.68	\$1,161,000	\$9.50	\$2,165,296	\$12.21
TOTAL CONSTRUCTION COST ( inc. VE )	\$51,148,682	\$601.75	\$53,912,677	\$440.92	\$88,777,149	\$500.52
COST PER SF	\$601.75		\$440.92		\$500.52	

COST LEVERAGING:	FORT RIVER	COST/SF	ADJUSTED COST PER SF		MAPLE	COST/SF
	ELEM. SCHOOL		WILDWOOD	COST/SF	ELEM. SCHOOL	
DELETE PV	(\$4,177,080)	(\$49.14)			(\$339,150)	(\$1.91)
ADD ESCALATION TO 4 TH QTR 2020	0	0	12%	\$52.91	5%	\$25.03
ADD CHPTR 149 A CM	0	0	\$0	0	5%	\$41.89
LEVERAGED COST PER SF		\$552.61		\$493.84		\$565.52
* Note Fort River cost per sf is \$27 - \$34 per sf more than Wildwood and Maple Ele.						



- **Energy Use Intensity**
- **HVAC System Maintenance Costs**
- **Utility Costs**
- **Carbon Emissions**
- **Procurement Strategy**
- **Construction Duration**
- **Project Costs**




# Fort River School| Cost Case Study Option A

**Energy Use Intensity :** 30  
Mechanical System: #5 Chilled Beam with Air Source Heat Pump

**HVAC Maintenance Cost :** High

**Utility Cost per Year:** \$0 (+fixed customer charges, systems benefit and demand charges and energy efficiency reconciliation)

**Carbon Emissions:**  
Scope I – Directly released by the building systems: 0 kg/yr  
Scope II – Emitted in the production of electricity used: 0 kg/yr  
Scope III – Includes Embodied energy in building materials : High\*  
(\*design strategies to reduce embodied carbon will be employed)



**Construction Duration and Phasing:** 22 months

**Procurement Strategy :** GC

Construction Cost: PVs owned (leased)	\$46,679,296 549/SF	(\$44,224,950) (\$520/SF)
<b>Project Cost: PVs owned (leased)</b>	<b>\$58,349,120</b>	<b>(\$55,281,187)</b>



# Fort River School| Cost Case Study Option C

DRAFT

**Energy Use Intensity** : 50  
Mechanical System: #5 Chilled Beam with Air Source Heat Pump

**HVAC Maintenance Cost** : High

**Utility Cost per Year**: \$120,000 – 150,000/yr (all-electric – 900,000 kWh)

**Carbon Emissions**:  
Scope I – Directly released by the building systems: 0 kg/yr  
Scope II – Emitted in the production of electricity used: 225,000 kg/yr  
Scope III – Includes Embodied energy in building materials : Medium\*  
(\*design strategies to reduce embodied carbon will be employed)

**Construction Duration and Phasing**: 28 months

**Procurement Strategy** : CM

Construction Cost: PVs owned (leased)	\$39,891,866	\$469/SF	(\$38,443,999) (\$452/SF)
<b><u>Project Cost</u></b> : PVs owned (leased)	<b>\$49,864,833</b>		<b>(\$48,054,998)</b>





# Fort River School| Cost Case Study Option E

**Energy Use Intensity** : 50  
Mechanical System: #6 Variable Air Volume and retain existing boilers

**HVAC Maintenance Cost** : High

**Utility Cost per Year**: \$53,773/yr (25,000 therms – 400,000 kWh)

**Carbon Emissions**:

Scope I – Directly released by the building systems:	132,500 kg/yr
Scope II – Emitted in the production of electricity used:	100,000 kg/yr
Scope III – Includes Embodied energy in building materials :	Low*

(\*design strategies to reduce embodied carbon will be employed)

**Construction Duration and Phasing**: 36 months and requires temp. construction.

**Procurement Strategy** : CM

Construction Cost:	\$37,803,173	\$445/SF
<b><u>Project Cost</u></b> :	<b>\$47,253,966</b>	





## Fort River School | **Case Study Factors**

- **Energy Use Intensity :** **30 - 50**
- **HVAC System Maintenance Costs :** **Low - High**
- **Utility Costs :** **\$0 - \$150,000/yr**
- **Carbon Emissions**
  - **Scope I :** **0 – 132,500 kg/yr**
  - **Scope II :** **0 – 225,000 kg/yr**
  - **Scope III :** **Low - High**
- **Procurement Strategy :** **GC or CM**
- **Construction Duration :** **22 – 36 months**
- **Project Costs :** **\$48 - \$58 Million**